

**Indoor Air Quality
Program**

Hopatcong Borough Schools

Hopatcong, New Jersey

2021-2022 School Year

Policy and Administration

This notice is to inform employees that our agency complies with the Public Employees Occupational Safety and Health (PEOSH) Program, Indoor Air Quality (IAQ) Standard (N.J.A.C. 12:000-13)(2007), which was proposed on December 18, 2006 and adopted on May 21, 2007.

We recognize that good indoor air quality is essential to employee's health and productivity. We have established the following policies to promote good indoor air quality for employees in our buildings. These policies follow the requirements established by the PEOSH IAQ Standard as it applies to our workplace. This Written Indoor Air Quality Program applies to the following Buildings/locations:

Hopatcong High School Tulsa Trail School
Hopatcong Middle School Durban Avenue School
Hopatcong Board of Education Administration Building

Designated Person

As required by the New Jersey PEOSH Indoor Air Quality Standard, a person has been designated as the person responsible for (Employer)'s compliance with the standard.

This person is:

Mr. Matthew Geary 973-770-8840
Designated Person *Phone#*

The designated person is the person who has been trained and given the responsibility by (Employer) to make routine visual inspections, oversee preventive maintenance programs, and maintain required records in order to ensure compliance with the IAQ Standard. The designated person is also assigned to receive employee concerns/complaints about indoor air quality, conduct investigations, facilitate repairs or further investigation as necessary, maintain required records, and update the written program annually.

Preventive Maintenance Schedule

Preventive maintenance schedules that follow manufacturers' specifications are in place for heating, ventilation and air conditioning systems (HVAC) systems in this workplace. A copy of the preventive maintenance schedule is attached. Damaged and inoperable components will be repaired or replaced as appropriate and a work order to show actions taken will be completed.

Recordkeeping

Documentation of preventive maintenance and repairs to the ventilation system are retained for at least 3 years and include the following information:

- Date that preventive maintenance or repair was performed
- Person or company performing the work
- Documentation of:
 - Checking and/or changing air filters
 - Checking and/or changing belts
 - Lubrication of equipment parts
 - Checking the functioning of motors
 - Confirming that equipment is in operating order
 - Checking for microbial growth in condensate pans or standing water

Documentation of preventive maintenance and work orders for repairs are maintained by *(Designated Person)*

Indoor Air Quality Compliance Documents

Our agency will make reasonable efforts to obtain and maintain copies of IAQ compliance documents. Available IAQ compliance documents will be maintained by the Designated Person and will be available to PEOSH during an inspection. These documents include:

1. As-built construction documents
2. HVAC system commissioning reports
3. HVAC systems testing, adjusting, and balancing reports
4. Operations and maintenance manuals
5. Water treatment logs
6. Operator training materials

Investigating Complaints

If employees begin to experience health symptoms that they believe are related to poor indoor air quality, they should notify the Designated Person so that their concerns can be investigated.

The Designated Person has been trained and given the authority to conduct basic indoor air quality complaint investigations. In many cases IAQ complaints can be resolved by the Designated Person.

Responding to Signed Employee Complaints to PEOSH

If we receive a written notification from PEOSH that a signed employee complaint has been filed with PEOSH, we will conduct an inquiry into the allegations. The findings of the initial inquiry and any planned actions will be provided in a written response to PEOSH within fifteen (15) working days of receipt. Copies of all responses to PEOSH will be maintained by the Designated Person.

Notification of Employees

The Designated Person will notify employees at least 24 hours in advance or promptly in emergency situations, of work to be performed on a building that may introduce air contaminants into their work area. This notification will be in writing and will identify the planned project and the start date. The notification will also include information on how to access Material Safety Data Sheets (MSDS) or other hazard information. The Designated Person will maintain records of this notification for compliance recordkeeping purposes.

Controlling Microbial Contamination

Uncontrolled water intrusion into building (roof leaks, flooding, pipe condensation, plumbing leaks, or sewer backups) has the potential to support microbial growth. All employees should routinely observe their workplace for evidence of water intrusion (i.e. roof leaks, pipe leaks). Employees should notify the Designated Person immediately if they observe evidence of water intrusion so that corrective action can be taken. Ceiling tiles, carpet, and wall boards not dried within 48 hours may be removed as directed by the Designated Person.

Controlling Air Contaminants

Outside air

The Designated Person will identify the location of outside air intakes and identify potential contamination sources nearby, such as loading docks or other areas where vehicles idle, nearby exhaust stacks, or vegetation. Periodic inspections will be conducted to ensure that the intakes remain clear of potential contaminants. If contamination occurs, the Designated Person will eliminate the contaminant source or make arrangements to relocate the intake.

Point Source Contaminants

The Designated Person will identify point sources of contaminants and arrange to capture and exhaust these sources from the building using local exhaust ventilation. Exhaust fans will be periodically inspected to ensure that they are functioning properly and exhausting to areas located away from outside air intakes.

Before selection and use of paints, adhesives, sealants, solvents or installation of insulation, particle board, plywood, floor coverings, carpet backing, textiles, or other materials in the course of renovation or construction, the designated person will check product labels or seek and obtain information from the manufacturer of those products on whether or not they contain volatile organic compounds such as solvents, formaldehyde or isocyanates that could be emitted during regular use. This information should be used to select the least volatile/hazardous product and to determine if additional necessary measures need to be taken to comply with the objectives of this section. The Designated Person will maintain records of this evaluation for compliance recordkeeping purposes.

Management and the Designated Person will consider the feasibility of conducting renovation/construction work using appropriate barriers, during periods when the building is unoccupied, or temporarily relocating potentially affected employees to areas of the building that will not be impacted by the project.

Temporary barriers will be utilized to provide a physical isolation between the construction area and occupied areas of the building.

Mechanical ventilation (i.e. fans, portable blowers, or existing HVAC equipment) will be used to maintain a negative pressure gradient between the work area and occupied areas to ensure the safety of employees. Renovation areas in occupied buildings will be isolated and dust and debris shall be confined to the renovation or construction area.

If work is being performed by an outside contractor, the Designated Person will maintain communication with contractor personnel to ensure they comply with the requirements of the PEOSH IAQ standard.

Employees who have special concerns about potential exposure during or after renovation/construction/repair work should consult with their supervisor. If despite these preventive actions, employees are exposed to air contaminants resulting in health effects, employees will be instructed to report any work-related health symptoms to one person (e.g., the nurse, human resources, designated person) so that they can accurately assess and investigate when indicated. All exposures should also be reported to their supervisor and the designated person.

Obtaining Permits and Performing Work in Accordance with the New Jersey Uniform Construction Code (N.J.A.C.5:23)

Permits for renovation and construction-related work will be obtained as required by the New Jersey Uniform Construction Code (NJUCC), (N.J.A.C. 5:23). All work requiring a permit will be performed in compliance with N.J.A.C. 5:23, Additional information concerning the NJUCC can be obtained from the NJ Department of Community Affairs, Division of Codes and Standards (www.state.nj.us/dca/codes, 609-984-7609)